

**MODOC JOINT UNIFIED SCHOOL DISTRICT
GEOTHERMAL INJECTION WELL
ADDENDUM # 2**

MODOC JOINT UNIFIED SCHOOL DISTRICT
906 WEST FOURTH STREET
ALTURAS, CA 96101

ADDENDUM # 2

Issue date of Addendum: November 18, 2015

To all Contract Holders of: Geothermal Injection Well Project

CHANGE CONTRACT DOCUMENTS:

Please modify the contract documents as noted below:

SECTION III – CONTRACT CONDITIONS

Supplementary Conditions

Please add the following items to the Supplementary Conditions:

13. Contractor will be required to provide 600 feet of 8" temporary piping for use during the test/flow pumping.
14. The Owner will provide a disposal area for the cuttings. Contractor will be required to haul the cuttings up to 2 miles to the disposal site.
15. Sound blankets or muffled equipment will be required during all drilling operations. Sound should not exceed 75 decibels along the east right-of-way line of Warner Street.
16. A red strobe light is required on the drill tower and any crane equipment.

The Bidder is instructed to acknowledge receipt of this Addendum.

Signature

Date

**A SIGNED COPY OF THIS ADDENDUM MUST BE SUBMITTED WITH THE
BID DOCUMENTS.**